

Presentation to the SRS Citizens Advisory Board Waste Management Committee

Alternative Storage of Vitrified Waste Canisters: Canister Interim Storage Project (CISP)

June 12, 2012

www.em.doe.gov

Jean M. Ridley, P.E. Federal Project Director DOE-SR/AMWDP



Acronyms

- CISP Canister Interim Storage Project
- CISC Canister Interim Storage Container
- CISCC Canister Interim Storage Container Carrier
- CTS Canister Transfer Station
- DWPF Defense Waste Processing Facility
- GWSB Glass Waste Storage Building
- SCT- Shielded Canister Transporter





Discuss storage of vitrified high level waste canisters produced by the Defense Waste Processing Facility (DWPF)

Discuss the most promising storage alternative to a Glass Waste
Storage Building



Background

- Additional storage for vitrified high level waste canisters is needed by December 2016.
- A 3rd Glass Waste Storage Building (GWSB #3) has high upfront costs:

Total Project Cost Range:

\$96 - \$138 Million

SRS pursuing a lower cost alternative - impacts to the public and environment are less than or equal to that of existing GWSBs.

E*M* Environmental Management

🔹 cleanup

performance

safetv





www.em.doe.gov


closure

Alternatives Analysis

- > Alternatives Analysis was conducted:
 - GWSB #3 with an option to increase capacity to 3,000 canisters
 - Above grade cask storage
 - Additional options

Final Report issued January 17, 2012


- "SRS Dry Cask" Alternative selected for further development
- Based on commercial spent nuclear fuel dry storage concept





www.em.doe.gov


Alternatives Analysis – Up Front Cost Comparison



- Cask Options include: vertical or horizontal w/ shielding only, licensable, or NRC licensed
- Hanford Open Rack underground open vault cans stacked 2 high
- **GWSB** underground concrete vault with individual canister supports



Alternatives Analysis – Life Cycle Comparison





SRS Storage Alternative - Development/Decision

- Titled: Canister Interim Storage Project (CISP)
- Conceptual Design Prepared Feb May 2012
 - Define scope and prepare conceptual design drawings (~5% of total design)
 - > Perform risk assessment
 - > Prepare a preliminary hazards assessment
 - > Prepare schedule and cost estimates
 - Reduces risk by supporting more accurate cost estimates for all project scope



Canister Interim Storage Project

- Use existing Shielded Canister Transporter (SCT)
- Remove ~ 3000 lowest radiological dose canisters from GWSB #1 and #2



GWSB #1





Shielded Canister Transporter

www.em.doe.gov

CISC - Canister Interim Storage Container

- Concrete-reinforced with 30" wall x 12' diameter x 15.5' high
- 106 tons empty; 126 tons w/7 canisters
- Safety: Preliminary analysis indicates mass, low center of gravity, and height-todiameter ratio, CISC will not tip during high winds or a tornado and cannot be significantly damaged by missiles. Seismically safe configuration.



Not licensed for shipment

safetv




E M Environmental Management

🔹 performance 🚸 cleanup 💠 closure


www.em.doe.gov

CISP – Canister Transfer Station & Carrier

- Shielded Canister Transporter (SCT) will remove canister from GWSB and transport canister to Canister Transfer Station (CTS)
- SCT will place 7 canisters into the container in the CTS
- Carrier will move container to storage pad










www.em.doe.gov

closure

10

Proposed CISP Site Plan



Alternative Storage of Vitrified Waste - Conclusion

www.em.doe.gov

- DOE Reviewed Multiple Alternatives for Storage
 - Upfront costs of GWSB #3 are not supported by out year budget projections
 - Other safe storage options provide opportunity for improved cash flow and lower overall costs
 - Above ground storage option developed Canister Interim Storage Project (CISP)
- Next step Selection of Preferred Alternative
- Projected path forward:

safetv

- FY 13 Design Start
- FY 14 Long-Lead Procurement Start
- ➢ FY 15 − Construction Start
- ➢ FY 16 Ready for Operations





E_{**M**} Environmental Management

◆ performance ◆ cleanup ◆ closure