

System Plan Revision 19









We do the right thing.



SRS Citizen's Advisory Board

Recommendation No. 15

January 23, 1996

High Level Waste Tank Farm Closure

The Savannah River Site Citizens Advisory Board (SRS CAB) understands that the Department of Energy-Savannah River Operations (DOE-SR) is currently undergoing a re-engineering program for the SRS high-level waste program. A concern of the SRS CAB is the criteria that will determine the final disposition of the high-level waste tanks and piping and header systems for the movement of high-level wastes between the reprocessing canyons, the tanks and the Defense Waste Processing Facility (DWPF). This criteria is yet to be determined; however, closure cannot begin until the criteria has been established (e.g., the allowable amount of waste left in the tanks at closure, disposition of the tanks, and tank systems at closure).

Mindful of this situation, the CAB recommends that:

- Criteria be established to close the tank farms by the end of FY1996 (September 30, 1996). A strategic closure plan to meet the criteria for the tank farms should also be drafted by the end of FY1996, and updated annually thereafter.
- The closure criteria and the strategic plan should be reviewed by an independent scientific peer review (ISPR) whenever there are significant changes to the closure criteria.



Agenda

- Liquid Waste System Overview/Status
- Liquid Waste System Plan
- Revision 19 Inputs & Assumptions
- Revision 19 Results
- Summary

SRS Liquid Waste Program Savannah River Remediation Legend: Actinide Removal Process ARP Nuclear Material **Operational Goals** Disposition **BWRE Bulk Waste Removal Efforts DWPF** Defense Waste Processing Facility √ Radionuclides to glass MCU Modular Caustic Side Solvent Extraction Unit Legacy √ Chemicals to Saltstone **SWPF** Salt Waste Processing Facility BA Liquid √Tanks closed Waste 43 tanks, 37 million gallons (Mgal), 280 Salt waste million curries (MCi) Actinide Removal 7.0 million gallons Process (ARP) (Mgal) treated Salt Sludge waste **Processing** 3.7 million gallons Modular Caustic Side (Mgal) treated Salt Waste Processing Facility Solvent Extraction Defense Waste (under construction) Unit (MCU) **Processing Facility** Radionuclides **Tanks** Cleaned and Closed Inert chemicals <1% radionuclides remain in tanks << 1% radionuclides 51 Tanks Glass Waste Storage to saltstone >99% radionuclides · 6 grouted & closed · 2 heel removal complete to glass · 6 Bulk Waste Removal Efforts (BWRE) complete 16 million gallons (Mgal) grout 70% empty (old style) Poured 3,833 cans of projected 8,582 dispositioned containing 414 (kCi) 14% empty (new style) 53 million curies immobilized in glass



Safe receipt from H-Canyon, treatment, and disposition of SRS liquid waste requires synchronization of several highly interdependent nuclear facilities and chemical operations



System Planning

- Changes to System Plans are driven by:
 - Advances in Technology
 - Change in Sequencing
 - Acceleration Opportunities
 - Funding Adjustments




System Plan Revision 19

- August 2013 inputs and assumptions (modified April 2014 & May 2014) for Revision 19 of the Liquid Waste System Plan:
 - \$407.1M new Budget Authority (BA) to the LW contractor in fiscal year 2014
 - \$430M/yr (constant dollar funding) to the Liquid Waste contractor fiscal year 2015-fiscal year 2019
 - Includes Line Item funding, including assigned contingency, for Saltstone Disposal Units beginning with Saltstone Disposal Unit-7
 - Includes Glass Waste Storage Project Line Item beginning in fiscal year 2015
 - \$525 M (in fiscal year 2020 and escalated thereafter) per year until the end of the program.
 - Includes \$80M/yr (in fiscal year 2020 and escalated thereafter) for operation of Salt Waste Processing Facility.



System Plan Revision 19



- Using these inputs, two significant impacts of the lower funding levels are realized:
 - Salt Waste Processing Facility is not supported at its rated capacity upon startup
 - After grouting Tanks 5, 6, 12, & 16 no tanks are grouted until 2024



System Plan Revision 19 Specific Results

- Salt Waste Processing Facility operations not supported at rated capacity
 - Sufficient salt batch blend tanks not available at Salt Waste Processing Facility startup
 - Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit operations limited due to funding and Saltstone Disposal Unit space
 - Funding for Defense Waste Processing Facility enhancements not available until fiscal year 2020 with completion in 2022
 - Enhanced Low Activity Waste Disposal II enhancements and increased staffing at Saltstone not funded until fiscal year 2024
 - Inability to afford sludge waste removal at a pace sufficient to support desired canister and salt throughput
 - Limited canister storage locations prior to completion of the Glass Waste Storage Project
- Comparison of Salt Waste Processing Facility capability versus predicted throughput modeling shows a cumulative difference of over 18 million gallons between fiscal year 2019 and fiscal year 2024, representing an additional two years to the Liquid Waste lifecycle

Fiscal Year	SWPF Capacity	Rev 19	Delta
FY19	4.625 Mgal	4 Mgal	-0.625 Mgal
FY20	7.2 Mgal	3 Mgal	-4.2 Mgal
FY21	7.2 Mgal	3 Mgal	-4.2 Mgal
FY22	9 Mgal	6 Mgal	-3 Mgal
FY23	9 Mgal	6 Mgal	-3 Mgal
FY24	9 Mgal	6 Mgal	-3 Mgal
Total	46.025 Mgal	28 Mgal	-18.025 Mgal



System Plan Revision 19 Specific Results (Continued)

We do the right thing.

Tank Closure Activities

- Grouting of Tanks 5 and 6 completed in fiscal year 2014
- Grouting of Tanks 16 and 12 to be complete in fiscal year 2016 (Federal Facilities Agreement date: fiscal year 2015)
- Given the Revision 19 inputs, next tank grouting occurs in 2024

· Interim Salt Processing

- Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit operations provide tank space for preparation of sludge batches for Defense Waste Processing Facility, support of waste receipts from H-Canyon, progress towards closure of old-style tanks, and support of Salt Waste Processing Facility upon startup in 2018.
- Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit will utilize Next Generation Solvent
- Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit throughput is determined by:
 - Operator staffing levels at Saltstone & Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit
 - · Availability of Saltstone Disposal Unit space
 - · Availability of canister storage
 - Funding to perform sludge waste retrievals
- Salt processing at Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit will continue until 6 months prior to Salt Waste Processing Facility startup then shutdown for transfer line modifications to tie SWPF in to the Liquid Waste System

Fiscal Year	ARP/MCU Production Forecast (kgal)
FY14	800
FY15	1,500
FY16	1,200
FY17	2,000
FY18	1,000




System Plan Revision 19 Specific Results (Continued)

We do the right thing.

Sludge Processing

- Defense Waste Processing Facility canister production synchronized with Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit production.
- Glass Waste Storage Building 2 had 822 available canister storage locations at start of fiscal year 2014
- Limited storage capacity in Glass Waste Storage Building 2, and expected timing of the Glass Waste Storage Project line item, limits Defense Waste Processing Facility operation until fiscal year 2019.
- Bulk sludge waste retrievals and sludge batch washing and qualification are limited to just-in-time supply



Fiscal Year	Expected Canister Production
FY14	125
FY15	155
FY16	135
FY17	170
FY18	160
FY19	275
FY20	275
FY21	275
FY22	275
FY23	275



System Plan Revision 19 Specific Results (Continued)

We do the right thing.

- Saltstone Disposal Unit Construction
 - Saltstone Disposal Unit required to support grout production and salt treatment at either Actinide Removal Process/Modular Caustic-Side Solvent Extraction Unit or Salt Waste Processing Facility
 - Without available Saltstone Disposal Unit space, Salt treatment cannot occur
 - Saltstone Disposal Unit construction costs have significant impact to overall funding profile

- Saltstone Disposal Unit must be available as follows to prevent impacting planned salt processing:

Saltstone Disposal Unit	Need Date
Saltstone Disposal Unit 6	May 2017
Saltstone Disposal Unit 7	October 2021
Saltstone Disposal Unit 8	December 2023
Saltstone Disposal Unit 9	September 2025





Revision 19 Results

Parameter	Revision 18	Revision 19
Final Type I, II, and IV tanks Bulk Waste Removal Efforts complete	2023	2028
Final Type I, II, and IV tanks complete operational closure	2028	2032
Complete bulk sludge treatment	2026	2030
Complete bulk salt treatment	2028	2033
Complete heel treatment	2032	2039
Small Column Ion Exchange for supplemental salt waste treatment	Yes	No
Next generation extractant for increased Salt Waste Processing Facility throughput	Yes	Yes
Maximum canister waste loading	40 wt%	40 wt%
Nominal annual canister throughput rate	275	275
Total number of cesium-only canisters produced	0	0
Radionuclides (curies) dispositioned in Saltstone Disposal Facility within Liquid Waste Strategy	Yes	Yes



Alternative Case

We do the right thing.

 Maximize salt treatment by supporting Salt Waste Processing Facility at rated capacity



Maximize Salt Waste Processing Facility Throughput

We do the right thing.

Scope

- Defense Waste Processing Facility Enhancements, Enhanced Low Activity Waste Disposal Phase II,
 Saltstone Production Facility @ 24/7, Accelerate Sludge Bulk Waste Removal Efforts
- Enhance Actinide Removal Process / Modular Caustic-Side Solvent Extraction Unit production
- Accelerate Saltstone Disposal Unit Construction
- Increase Glass Waste Storage Building #1 capacity

Results

Fiscal	Rev 19	Alt Case	Rev 19	Alt Case
Year	ARP/MCU	ARP/MCU	SWPF	SWPF
FY14	800	800		
FY15	1,500	1,500		
FY16	1,200	1,200		
FY17	2,000	4,700		
FY18	1,000	2,350		
FY19			4,000	4,625
FY20			3,000	7,200
FY21			3,000	7,200
FY22			6,000	9,000
FY23			6,000	9,000
FY24			6,000	9,000
Total	6,500	10,550	28,000	46,025

Parameter	Rev 19	Alt Case
Final Type I, II, & IV tanks Bulk Waste Removal Efforts complete	2028	2027
Final Type I, II, & IV tanks grout complete	2032	2031
Complete bulk sludge treatment	2030	2028
Complete bulk salt treatment	2033	2031
Complete heel treatment	2039	2037
Small Column Ion Exchange for supplemental salt waste treatment	No	No



Revision 19 Addendum

- Currently under development Due August 15, 2014
- While maintaining risk reduction, emphasize removing waste from old-style tanks and providing enhanced capability for feeding Salt Waste Processing Facility



Summary

We do the right thing.

Lessons Learned from Revision 19 modeling:

- Importance of Salt Waste Processing Facility in lifecycle planning
- Importance of near term salt processing
- Need for Salt Waste Processing Facility support projects
- Need/Importance of Saltstone Disposal Units



Acronyms

We do the right thing.

ARP Actinide Removal Process
BWRE Bulk Waste Removal Efforts

DOE Department of Energy

DOE-EM Department of Energy - Environmental Management

DWPF Defense Waste Processing Facility
ELAWD Enhanced Low Activity Waste Disposal

FFA Federal Facilities Agreement

FY Fiscal Year (October 1st - September 30th)

GWSP Glass Waste Storage Project
GWSB Glass Waste Storage Building
LWSP Liquid Waste System Plan

MCi Million Curies

MCU Modular Caustic-side Solvent Extraction Unit

Mgal Million Gallons

NGS Next Generation Solvent
SCIX Small Column Ion Exchange
SDI Salt Disposition Integration
SDU Saltstone Disposal Unit

SPF Saltstone Production Facility

SRR Savannah River Remediation, LLC

STP Site Treatment Plan

SWPF Salt Waste Processing Facility