



A URS COMPANY TEAMED
WITH BECHTEL | CH2M HILL | B&W | AREVA

We do the right thing.

Z Area Salt Disposal Facility Update

Presentation to the Waste Management Committee



August 12, 2014

Mike Borders

Defense Waste Processing Facility/Saltstone Facility Manager

We do the right thing.

- Fulfill a 2014 Waste Management Committee Work Plan topic.



We do the right thing.

- Savannah River Site's (SRR) Z Area Saltstone Facility
 - Status of Saltstone Disposal Facility Vault 4
 - Low-level radioactive contamination at Storm Water Outfall Z-01
- Actions SRR has and is taking to address these issues



Saltstone Disposal Facility



Location of Saltstone Disposal Facility at SRS



Saltstone Disposal Facility (SDF)

Vault 4 Water Intrusion

We do the right thing.

- Cracks in Vault 4 roof allowed rainwater to migrate into the vault
- Liquid collected in the narrow annular space between the grout waste form and the vault wall
- Contaminated liquid could weep through construction joints or cracks that existed in the vault wall





Existing Vault 4 Contamination Controls

We do the right thing.




- **Prevent Rainwater Intrusion into Vault (Roof Coatings, Sealants)**
- **Control Rainwater Flow Path**
 - Gutters on roof and weather enclosures
 - Grading to route rainwater to retention basin
- **Fix Wall Contamination**
- **Manage Drain Water Levels Inside Vault**
 - Drain water return system
 - Manage cell water level below hut level to prevent release of contamination to environment
- **Containment**
 - Weather enclosures up to 8'
 - Troughs to collect leakage
 - Isolate from rainwater
 - Installed Megamix coating on walls
 - Installed Xypex coating on walls



Vault 4 Stabilization


We do the right thing.

- **Last Vault 4 disposal operation in 2012**
 - Current disposal operations utilize new design cylindrical SDUs
- **Several alternatives were evaluated to:**
 - Eliminate rainwater infiltration to Vault 4
 - Mitigate worker and environmental risks
- **Alternative selected:**
 - Pour minimum “clean cap” to Vault 4 cells as necessary to establish roof dose rate <5 mrem/hr for worker exposure control
 - Install elastomeric roof covering on cells D, E, F, J, K, and L
 - Cells A, B, C, G, H, and I are already coated/sealed
 - Continue maintenance on roof and weather enclosures
 - Continue to manage drain water levels



We do the right thing.

- **SRR and DOE are committed to Vault 4 Stabilization Plan**
 - Project fully funded and ahead of schedule
- **Clean cap and elastomeric roof coating of three cells (J, K & L) scheduled in FY14**
 - Roof coating material determined
 - Testing of low-bleed grout mixtures completed and mix selected
 - Capping of Cells J, K and L complete
 - Capping of cell D in progress (ahead of plan)
 - Roof coating completed on cells J and K with cell L in progress
- **Capping and coating of remaining cells (D, E & F) planned to complete by February 2015**



Z Area Retention Basin Contamination

We do the right thing.



Rainwater carried contamination from Vaults 1 and 4 area to the Storm Water drain line

- Drain line flows to Basin No. 4



Basin No. 4 only discharges if level reaches the height of spillway

- Feb 2013 first observed basin discharge



Spillway from Basin No. 4 flows to Storm Water Outfall Z-01

- Low-level contamination deposited



Storm Water Outfall Z-01 flows to McQueen's Branch

- Sedimentation breaks installed to minimize contamination spread

We do the right thing.

- **Sedimentation basin being expanded to 100-year storm event size**
 - Excavation began on June 12, 2014
 - Expansion projected to be completed in September 2014
- **Storm Water Outfall**
 - Completed work to excavate spots of contaminated soil in accordance with DOE Order 458.1 and consistent with the SDF Solid Waste Permit
- **Radioactive effluent monitoring at Outfall and McQueen's Branch continues with no increases detected (sampled when liquid present)**

